

Yuba IRWMP – HIC-05

Project Short Form¹

Please fill out the following information to the best of your ability/knowledge. Contact Keri Rinne with questions: keri.rinne@gmail.com

PROJECT SPONSOR INFORMATION

| | |
|--------------------------------|--|
| Lead Agency/Organization | Hallwood Irrigation Company |
| Name of Primary Contact(s) | Mark Chandless |
| Mailing Address | P.O. Box 1349, Marysville, CA 95901 |
| Email Address | mchandless@att.net |
| Phone (###) ###-#### | 530-788-3289 |
| Project Partners/Collaborators | Yuba Water Agency |
| YWA Liaison | Joanna Lessard; Ryan McNally |

GENERAL PROJECT INFORMATION

| | |
|--|--|
| Project Title | Seepage Loss Prevention |
| Project Total Budget (Attach detailed budget, if available) | \$5,696,000 |
| Budget Breakdown | Planning/Design Budget: \$0. Implementation Budget: \$5,696,000 |
| Project Funding Match , if any | TBD |
| Total Project Funding Need | TBD |
| Project Location (Attach map if available) | Hallwood, Yuba County |
| Watershed/subwatershed | |
| Groundwater Basin (Select one) | <input checked="" type="checkbox"/> North Yuba Subbasin <input type="checkbox"/> South Yuba Subbasin <input type="checkbox"/> Not Applicable |
| Supports Yuba Groundwater Sustainability Plan (GSP)? | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| Measurable Objective(s) Benefit (Answer If 'Yes' above) (check <i>all</i> that apply) | <input checked="" type="checkbox"/> Chronic lowering of groundwater levels <input checked="" type="checkbox"/> Reduction of groundwater storage <input checked="" type="checkbox"/> Degraded water quality <input checked="" type="checkbox"/> Land subsidence <input checked="" type="checkbox"/> Depletions of interconnected surface waters |
| Project Priority (Select one) | <input checked="" type="checkbox"/> High <input type="checkbox"/> Medium <input type="checkbox"/> Low |
| Project Type (check <i>all</i> that apply) | <input type="checkbox"/> Conceptual <input type="checkbox"/> Feasibility Study <input type="checkbox"/> Study/Assessment <input type="checkbox"/> Planning <input type="checkbox"/> Engineering/Design <input type="checkbox"/> Permitting <input type="checkbox"/> CEQA/NEPA <input checked="" type="checkbox"/> Facility Construction <input checked="" type="checkbox"/> Restoration <input type="checkbox"/> Monitoring <input type="checkbox"/> Best Management Practices <input type="checkbox"/> Acquisition |

¹ Completed Project Short Forms should be sent via email to Keri Rinne at keri.rinne@gmail.com

| | |
|------------------------|--|
| | <input type="checkbox"/> Demonstration/Pilot Project |
| Legal Authority | |

Please select the *status* of the CEQA/NEPA/Permitting for this project:

| | |
|-----------------------------------|--|
| CEQA (Select one) | <input checked="" type="checkbox"/> Exempt <input type="checkbox"/> Not Started <input type="checkbox"/> Initial Study <input type="checkbox"/> EIR <input type="checkbox"/> Determination <input type="checkbox"/> Unknown if Required |
| NEPA (Select one) | <input checked="" type="checkbox"/> Exempt <input type="checkbox"/> Not Started <input type="checkbox"/> Environmental Assessment <input type="checkbox"/> EIS <input type="checkbox"/> Record of Decision <input type="checkbox"/> Unknown if Required |
| Permitting (Select one) | <input checked="" type="checkbox"/> Not Required <input type="checkbox"/> Not started <input type="checkbox"/> Identified <input type="checkbox"/> Consultations Complete <input type="checkbox"/> Application Submitted <input type="checkbox"/> Complete <input type="checkbox"/> Unknown if Required |

PROJECT DESCRIPTION

Write a narrative briefly describing the project components and/or characteristics (Suggest ~ 300 words).

The Hallwood Irrigation Company (HIC) received a Community Impact Grant from the Yuba Water Agency (YWA) for the HIC System Renovation Plan. The first phase of the Renovation Plan included the development of an irrigation system condition assessment, which was completed in December 2022. The condition assessment identified several recommended improvements and prioritized these improvements. The second phase of the Renovation Plan includes developing the construction documents, engineering, and permitting for the highest priority improvements. The project identified herein was identified as the 5th highest priority out of the 12 improvement projects recommended.

The condition assessment identified several seepage problem areas: approximately 6,000 linear feet near the beginning of the North Main Ditch, approximately 4,000 linear feet along the Highway 20 Ditch, and approximately 7,000 linear feet along the Warehouse Ditch. This accounts for an estimated total of 17,000 linear feet of ditches that experience seepage issues. The exact linear footage must be refined pending surveys and hydraulic investigations to be performed during the design phases for each seepage loss prevention project. It is recommended to phase the construction of seepage loss prevention projects to make it easier to secure funding for each identified canal section.

The recommended alternative for preventing seepage is to line the ditches with a geomembrane liner (such as reinforced polyethylene placed over a geotextile fabric or other composite materials).

A geomembrane liner could be placed along the canal banks exposed or covered in shotcrete or polymer concrete. It is recommended to cover the geomembrane liner with shotcrete or polymer concrete for this application because of the sediment removal practices employed by HIC. A polymer concrete would be able to cure in one day and would only require a 1-inch-thick layer, while shotcrete would require 28 days to fully cure and would need to be at least 3 inches thick. An 18-inch by 18-inch cross-section anchor trench would be required along the canal banks to tie-in the liner. The liner would need to be specified to be manufactured with geotextile layers on top and bottom to adhere to the soil and provide an interface for concrete application.

Geomembrane liners are typically sold with a 20-year warranty but can last upwards of 40 years when properly installed.

PROJECT RATIONALE/ISSUES STATEMENT

Briefly describe the need for the project and the desired outcomes/deliverables (Suggest ~ 200 words). Include an explanation of benefits and how they would be evaluated.

Seepage losses occur when water percolates through the ground underneath a canal. This results in increased irrigation demands and more diversion from the Yuba River or more groundwater pumping into the canal.

This project will prevent seepage and eliminate all water losses from the lined canal sections. Furthermore, ditch linings provide the added benefits of preventing erosion, improving canal water quality, and increasing the flow rate of water through the channel if the lining is installed exposed. Additionally, a ditch lining alternative would reduce the risk of bank blowout.

The two main goals are to (1) improve the efficient use of Yuba River surface water supplies in the area of benefit in the North Yuba Subbasin and (2) improve the quality and quantity of flow rate data to allow more precise and accurate control of flows in and diversions from the HIC irrigation system.

The project is expected to realize the following quantifiable benefits:

1. Water supply savings resulting from avoidance of excess surface water diversion.
2. Improved groundwater conditions due to greater availability of surface water supplies and subsequent reduced demand for groundwater.

Such water savings and resiliency will allow for continued avoidance of “deficit pumping” by these agencies. Furthermore, the water savings from the project will improve water supply conditions that allow the Yuba Subbasins water suppliers to implement their groundwater substitution transfer program which provides benefits during dry years to water suppliers throughout the state.