

Yuba IRWMP – RD10-05

Project Short Form¹

Please fill out the following information to the best of your ability/knowledge. Once the project has been received and a preliminary review completed, the project team will work with you to develop additional information.

Project Sponsor Contact Information

Lead Agency/Organization	Reclamation District No. 10
Name of Primary Contact(s)	Sarb Johl, President
Mailing Address	9274 HWY 70, Marysville, CA 95901
Email Address	
Phone (###) ###-####	Office: 530-682-9916
Project Partners/Collaborators	

General Project Information

Project Title	RD 10 – Feather River Reach F4a Seepage & Stability Mitigation
Project Total Budget, based on current knowledge	Reach F4a Alternative 1 Cost - \$500,000 Reach F4a Alternative 2 Cost - \$1,900,000 Total Project Cost - \$500,000 to \$1,900,000
Project Funding Match, if any	\$0
Total Project Funding Request	\$1,900,000
Can a detailed cost estimate be provided upon request?	Yes
Project Location (map if available)	Project location map available upon request.
City/Community	Marysville (RD 10)
Watershed/subwatershed	Sacramento Valley
Groundwater Basin	Sacramento Valley North Yuba 5-021.60
Project Type (highlight in gray all that apply)	Conceptual Feasibility Study Study/Assessment Planning Engineering/Design Permitting CEQA/NEPA Facility Construction Restoration Monitoring Best Management Practices Acquisition Demonstration/Pilot Project

¹ Completed Project Short Forms should be sent via email to Katie Burdick at admin@burdico.net **and** Elizabeth Herrera at Elizabeth.herrera@fishsciences.net

--	--

Project Description

Write a narrative briefly describing the project components and/or characteristics (maximum of 300 words).

In 2019, through a grant from YWA, RD 10 completed a Limited Geotechnical Problem Identification Report (PIR) to identify and prioritize geotechnical deficiencies and develop preliminary mitigation measures for the RD 10 basin. Reach F4a was identified as a critical reach and displayed through-seepage and landside slope stability concerns.

Reach F4a is an 850-linear foot (lf) reach along the left bank of the Feather River. The proposed project will complete design, permitting, CEQA/NEPA, land acquisition, and construction for the selected design alternative. The PIR developed two preliminary design alternatives for consideration, both of which meet geotechnical factors of safety for landside slope stability, and gradient criteria for through and underseepage.

The proposed alternatives consider either a drained stability berm, or a shallow (15ft) cutoff wall throughout the project reach.

I. Project Rationale/Issues Statement

Briefly describe the need for the project and the desired outcomes/deliverables (maximum of 200 words).

The RD 10 levees were initially constructed by the US Army Corps of Engineers as part of the Sacramento River Flood Control Project (SRFCP) from the early to mid-1900s. Over time, the levees have experienced numerous high-water events and performance related issues specifically along the Feather River. Typically, and as supported by the Limited Geotechnical PIR, the RD 10 levees experience seepage and sand boils during high water events. Additionally, 2 breaches occurred during the 1936-37 and 1937-38 flood seasons along the Feather River. In the absence of mitigation, flood risk due to seepage and stability concerns may lead to more broad levee safety concerns during high-water events, including breach.

The proposed project would reduce flood risk along Reach F4a due to the existing seepage and stability concerns.

Deliverables include: project alternative analysis, design, CEQA/NEPA analysis, permitting, land acquisition, and construction.